# PK3GTA1

Load center accessory, QO/Homeline, ground bar kit, 3 terminals





#### Main

Product line	QO Homeline	
Product type	Bar	

Complementary

Number of connectors	3	
Wire size	AWG 14AWG 4 copper AWG 12AWG 4 aluminium	
Provided equipment	2 screw	
Bar length	1.38 in (35 mm)	
Device mounting	Direct mounting back of enclosure	
Height	0.437 in (11.10 mm)	
Depth	0.312 in (7.92 mm)	

### Ordering and shipping details

US1DE3A00102
DE3A
785901156932
Yes
US

#### **Packing Units**

1 doking office	
Unit Type of Package 1	PCE
Number of Units in Package 1	1
Package 1 Height	0.40 in (1.016 cm)
Package 1 Width	0.78 in (1.982 cm)
Package 1 Length	1.35 in (3.429 cm)
Package 1 Weight	0.64 oz (18.144 g)
Unit Type of Package 2	CAR
Number of Units in Package 2	10
Package 2 Height	3.60 in (9.144 cm)
Package 2 Width	4.40 in (11.176 cm)
Package 2 Length	5.40 in (13.716 cm)
Package 2 Weight	8.64 oz (244.94 g)
Unit Type of Package 3	PAL
Number of Units in Package 3	4680
Package 3 Height	27.00 in (68.58 cm)
Package 3 Width	40.00 in (101.6 cm)

Package 3 Length	48.00 in (121.92 cm)
Package 3 Weight	288.00 lb(US) (130.634 kg)
Offer Sustainability	
Sustainable offer status	Green Premium product
California proposition 65	WARNING: Cancer and Reproductive Harm - www.P65Warnings.ca.gov
REACh Regulation	<sup>™</sup> REACh Declaration
REACh free of SVHC	Yes
EU RoHS Directive	Compliant EU RoHS Declaration
Toxic heavy metal free	Yes
Mercury free	Yes
China RoHS Regulation	<sup>™</sup> China RoHS Declaration
RoHS exemption information	₫Yes
Environmental Disclosure	Product Environmental Profile

## Contractual warranty

Circularity Profile

Warranty	18 months
----------	-----------

No need of specific recycling operations